CALL TOLL FREE 877-742-2878 FOR SALES AND SUPPORT

Return to BurtProcess.com

EBARA

Model EPD / OPTIMA

Pro Drainer™

sump, drainage



EBARA

EBARA Pumps Americas Corporation

Model EPD/OPTIMA

Features

- **High quality stainless steel** (*Note:* Optima has Noryl impeller)
- Available in 1/3, 1/2, 3/4, 1, 1 1/2 HP models • **Single and three phase models** available
- **Air filled, continuous duty rated**, permanent split capacitor motors • **Built-in thermal protection** with automatic reset (Single Phase Only)
- Built to **operate whether fully or partially submerged**
- **Oil lubricated double mechanical shaft seal** (1/2 - 1 1/2 HP models)
- **Temperature rating to 122°F/50°C**; 140°F/60°C intermittent duty
- **20' UL/CSA approved**, water resistant #16 AWG cord
- Capacities to 88 GPM, heads to 62 feet
- Optima slimline automatic models **can operate in a 12" diameter or 8" x 8" square basin**


Applications

- Residential
- Commercial
- Industrial
- Drainage
- Seepage
- Effluent/containment transfer
- Waste water (from trays, wet bars, washing machines)
- Empty water storage structures
- Decorative fountains
- Irrigation
- Mound systems, leach fields
- Move water/effluent to sewage systems

C US

***Note:** UL and CSA listed; Model Optima UL certified only.*

EPD, Optima selection chart



EBARA Pumps Americas Corporation
1651 Cedar Line Drive • Rock Hill, SC 29730 • telephone: (803) 327-5005 • fax: (803) 327-5097
www.pumpsebara.com
© 2018 EBARA Pumps Americas Corporation, *All rights reserved.*